

# Direct Light Tube 900 mm





Diffused LED light module to be installed in the Infra-Structure Episode 2. Safety fixing and locking mechanical elements integrated for a transversal installation between two rods of the profile. The Light Tubes are only fed by one of the ends and do not communicate current through the other end. Each lighting element is completed by...

Diffused LED light module to be installed in the Infra-Structure Episode 2.

Safety fixing and locking mechanical elements integrated for a transversal installation between two rods of the profile.

The Light Tubes are only fed by one of the ends and do not communicate current through the other end. Each lighting element is completed by a long 4m electrical cable equipped with an output microconnector.






## Main specifications

Number of heads	1	CRI	90
Lamp category	LED	Net lumen (lm)	1456
Power (W)	22W	Mountings	Ceiling surface
System power (W)	23	Environment	Indoor dry location
CCT (K)	2700K		,

### Optical


Lighting type Direct	
LED type Top LED	
<b>Light distribution</b> Symmetric	
Optical type Diffused ligh	١t
Beam angle (°) 150	
Beam angle C90-270 (°) 106	
Efficiency (lm/W) 63.3	



1456 lm

h(m)	E(Ix)	D(m)
1	357	7.49
2	89	14.98
3	40	22.47
4	22	29.96
5	14	37.45

Beam Angle: 150°



#### Electrical

Dimmable	res
Driver	Remote
	excluded
Emergency	Without
Insulation class	III

### **Physical**

Color	White
Orientation	Fixed
Weight (kg)	0.7
Length (mm)	900
Lifespan (L70 B10)	L80B50

# Direct Light Tube 900 mm







LED Power Supply Source for remote installation. 48V/320W. 100/240 Vac 60.8919

LED Power Supply Source for remote installation. 48V. 100Vac (150W)-240Vac (200W) 60.9607

LED power supply source for remote installation, 48V/120W. 220/240 Vac 60.9170







DALI 12-48V Dimmer 60.9678

0/1-10V & Push 12-48V Dimmer 60.9395

Casambi Controller 220-240V. Remote Installation 60.9392